09 28 Backing Boards and Underlayments 09 28 13 - Cementitious Backing Boards

			Labor-			2022 Bare Costs			Total	
09 28 13	3.10 Cementitious Backerboard	Crew	Output	Hours	Unit	Material	Labor	Equipment	Total	Incl 0&
0190	3' x 5' x 5/8" sheets	2 Carp	350	.046	S.F.	.93	2.57		3.50	4.
0200	3' x 6' x 5/8" sheets		350	.046		.99	2.57		3.56	4.
0250	On counter, 3' x 4' x 1/2" sheets		180	.089		1	5	į	6	8.
0260	3' x 5' x 1/2" sheets		180	.089		.73	5		5.73	8.
0270	3' x 6' x 1/2" sheets		180	.089		.73	5		5.73	8
0300	3' x 4' x 5/8" sheets		180	.089		.93	5		5.93	8.
0310	3' x 5' x 5/8" sheets		180	.089		.93	5		5.93	8
0320	3' x 6' x 5/8" sheets		180	.089	+	.99	5		5.99	8

09 29 Gypsum Board

09 29 10 - Gypsum Board Panels

00 00	10.30	Gypsum	Roard
UY 27	10.30	GVDSuill	bualu

09 29	9 10.30 Gypsum Board		, ,						
0010	GYPSUM BOARD on walls & ceilings	R092910-10							
0100	Nailed or screwed to studs unless otherwise noted								
0110	1/4" thick, on walls or ceilings, standard, no finish included	2	Carp 1330	.012	S.F.	.34	68	: 1.02	
0115	1/4" thick, on walls or ceilings, flexible, no finish included		1050	.015		.32	.86	1.18	
0117	1/4" thick, on columns or soffits, flexible, no finish included		1050	.015		.32	.86	1.18	1
0130	1/4" thick, standard, no finish included, less than 800 S.F.		510	.031		.34	1.77	2.11	3
0150	3/8" thick, on walls, standard, no finish included		2000	.008		.25	.45	.70	
0200	On ceilings, standard, no finish included		1800	.009		.25	.50	.75	1
0250	On beams, columns, or soffits, no finish included		675	.024		.25	1.33	1.58	
0300	1/2" thick, on walls, standard, no finish included	, ;	2000	.008		.25	.45	.70	
0350	Taped and finished (level 4 finish)		965	.017	Î	.30	.93	1.23	
0390	With compound skim coat (level 5 finish)		775	.021	į	.36	1.16	1.52	
0400	Fire resistant, no finish included		2000	.008	.	.46	.45	.91	ě.
0450	Taped and finished (level 4 finish)		965	.017		.51	.93	1.44	1
0490	With compound skim coat (level 5 finish)	Manage	775	.021		.57	1.16	1.73	
0500	Water resistant, no finish included		2000	.008		.33	.45	.78	1
0550	Taped and finished (level 4 finish)	!	965	.017		.38	.93	1.3	
0590	With compound skim coat (level 5 finish)		775	.021		.44	1.16	1.60	
0600	Prefinished, vinyl, clipped to studs	:	900	.018		.47	1 ;	1.47	
0700	Mold resistant, no finish included		2000	.008		.39	.45	.84	
0710	Taped and finished (level 4 finish)		965	.017		.44	.93	1.37	1
0720	With compound skim coat (level 5 finish)		775	.021		.50	1.16	1.60	I.
1000	On ceilings, standard, no finish included		1800	.009		.25	.50	.7:	I.
1050	Taped and finished (level 4 finish)		765	.021		.30	1.18	1.48	
1090	With compound skim coat (level 5 finish)		610	.026		.36	1.48	1.84	
1100	Fire resistant, no finish included	÷	1800	.009		.46	.50	.90	
1150	Taped and finished (level 4 finish)		765	.021		.51	1.18	1.69	
1195	With compound skim coat (level 5 finish)		610	.026		.57	1.48	2.0	
1200	Water resistant, no finish included	ļ	1800	.009		.33	.50	.8:	
1250	Taped and finished (level 4 finish)		765	.021		.38	1.18	1.50	
1290	With compound skim coat (level 5 finish)		610	.026		.44	1.48	1.9	
1310	Mold resistant, no finish included		1800	.009		.39	.50	.8	
1320	Taped and finished (level 4 finish)		765	.021		.44	1.18	1.6	
1330	With compound skim coat (level 5 finish)		610	.026		.50	1.48	1.99	
1350	Sag resistant, no finish included		1600	.010		.39	.56		
1360	Taped and finished (level 4 finish)	1	765	.021		.44	1.18	1.6	
1370	With compound skim coat (level 5 finish)		610	.026		.50	1.48	1.9	
1500	On beams, columns, or soffits, standard, no finish included		675	.024		.29	1.33	1.6	
1550	Taped and finished (level 4 finish)		540	.030		.30	1.67	1.9	7