

14 27 Custom Elevator Cabs and Doors

14 27 13 – Custom Elevator Cab Finishes

14 27 13.10 Cab Finishes		Daily Crew	Labor- Output	Hours	Unit	Material	2022 Bare Costs		Total	Total Incl O&P
					Ea.		Labor	Equipment		
3550	Stainless steel walls					4,325			4,325	4,750
3575	Stainless steel returns at door					1,250			1,250	1,375
4450	Hospital elevator cab finishes (based on 3,500 lb. cab size)									
4475	Aluminum eggcrate ceiling				Ea.	755			755	830
4500	Stainless steel doors					4,300			4,300	4,725
4525	Epoxy flooring					495			495	545
4550	Quarry tile flooring					960			960	1,050
4575	Textured rubber flooring				Ea.	690			690	755
4600	Stainless steel walls					4,900			4,900	5,375
4625	Stainless steel returns at door					965			965	1,075

14 28 Elevator Equipment and Controls

14 28 10 – Elevator Equipment and Control Options

14 28 10.10 Elevator Controls and Doors

0010 ELEVATOR CONTROLS AND DOORS										
2975	Passenger elevator options									
3000	2 car group automatic controls	2 Elev	.66	24.242	Ea.	3,750	2,275		6,025	7,475
3025	3 car group automatic controls		.44	36.364		5,750	3,400		9,150	11,400
3050	4 car group automatic controls		.33	48.485		10,000	4,525		14,525	17,700
3075	5 car group automatic controls		.26	61.538		15,100	5,750		20,850	25,100
3100	6 car group automatic controls		.22	72.727		23,000	6,800		29,800	35,400
3125	Intercom service		3	5.333		605	500		1,105	1,400
3150	Duplex car selective collective		.66	24.242		4,350	2,275		6,625	8,150
3175	Center opening 1 speed doors		2	8		2,175	750		2,925	3,475
3200	Center opening 2 speed doors		2	8		3,050	750		3,800	4,450
3225	Rear opening doors (opposite front)		2	8		4,650	750		5,400	6,200
3250	Side opening 2 speed doors		2	8		7,975	750		8,725	9,875
3275	Automatic emergency power switching		.66	24.242		1,325	2,275		3,600	4,800
3300	Manual emergency power switching		8	2		560	187		747	890
3625	Hall finishes, stainless steel doors					1,550			1,550	1,700
3650	Stainless steel frames					1,600			1,600	1,775
3675	12 month maintenance contract								4,425	4,425
3700	Signal devices, hall lanterns	2 Elev	8	2		565	187		752	895
3725	Position indicators, up to 3		9.40	1.702		365	159		524	635
3750	Position indicators, per each over 3		32	.500		98.50	47		145.50	178
3775	High speed heavy duty door opener					2,875			2,875	3,175
3800	Variable voltage, O.H. gearless machine, min.	2 Elev	.16	100		36,000	9,350		45,350	53,500
3815	Maximum		.07	229		80,500	21,400		101,900	120,000
3825	Basement installed geared machine		.33	48.485		16,300	4,525		20,825	24,700
3850	Freight elevator options									
3875	Doors, bi-parting	2 Elev	.66	24.242	Ea.	6,875	2,275		9,150	10,900
3900	Power operated door and gate	"	.66	24.242		27,600	2,275		29,875	33,800
3925	Finishes, steel plate floor					1,250			1,250	1,375
3950	14 ga. 1/4" x 4' steel plate walls					2,275			2,275	2,500
3975	12 month maintenance contract								3,400	3,400
4000	Signal devices, hall lanterns	2 Elev	8	2	Ea.	585	187		772	920
4025	Position indicators, up to 3		9.40	1.702		415	159		574	690
4050	Position indicators, per each over 3		32	.500		113	47		160	195
4075	Variable voltage basement installed geared machine		.66	24.242		23,100	2,275		25,375	28,800
4100	Hospital elevator options									
4125	2 car group automatic controls	2 Elev	.66	24.242	Ea.	3,750	2,275		6,025	7,475