# 32 32 Retaining Walls

32 32 13 - Cast-in-Place Concrete Retaining Wal	32	32 13	DOTAL .	Cast-in-Place	Concrete	Retaining	Walls
---	----	-------	---------	---------------	----------	-----------	-------

			Daily	Labor-			202	22 Bare	Costs		Total
32 32	2 13.10 Retaining Walls, Cast Concrete	Crew	Output	Hours	Unit	Material	Labor		Equipment	Total	Incl O&P
0010	RETAINING WALLS, CAST CONCRETE										
1800	Concrete gravity wall with vertical face including excavation & backfill										
1850	No reinforcing										
1900	6' high, level embankment	; C-17C	36	2.306	L.F.	116	137		25.50	278.50	360
2000	33° slope embankment	[ ]	32	2.594		136	. 154		28.50	318.50	410
2200	8' high, no surcharge	1 1	27	3.074		145	183		34	362	470
2300	33° slope embankment	1	24	3.458		175	206		38	419	545
2500	10' high, level embankment		19	4.368		207	260		48	515	670
2600	33° slope embankment	Ý	18	4.611	*	287	274		51	612	780
2800	Reinforced concrete cantilever, incl. excavation, backfill & reinf.										
2900	6' high, 33° slope embankment	C-17C	35	2.371	L.F.	106	141		26	273	360
3000	8' high, 33° slope embankment	1 1	. 29	2.862		123	170		31.50	324.50	425
3100	10' high, 33° slope embankment	1	20	4.150;		159	247		45.50	451.50	595
3200	20' high, 500 lb./L.F. surcharge	1 +	7.50	11.067	+	480	660	1	122	1,262	1,650
3500	Concrete cribbing, incl. excavation and backfill										
3700	12' high, open face	B-13	210	.267	S.F.	53	13	.25	9.95	76.20	89
3900	Closed face	· #	210	.267	"	50	13	.25	9.95	73.20	85.50
4100	Concrete filled slurry trench, see Section 31 56 23.20										
20 1	20.02 Sagmental Detaining Walls										

## 32 32 23 - Segmental Retaining Walls

#### 32 32 23.13 Segmental Conc. Unit Masonry Retaining Walls

			T FT T 1 71								
0010	5	SEGMENTAL CONC. UNIT MASONRY RETAINING WALLS									
7100		Segmental retaining wall system, incl. pins and void fill									
7120		base and backfill not included									
7140		Large unit, 8" high x 18" wide x 20" deep, 3 plane split	B-62	300	.080	S.F.	18.35	3.95	.88.	23.18	27
7150	1	Straight split	]	300	.080		18.30	3.95	.88	23.13	27
7160		Medium, lt. wt., 8" high x 18" wide x 12" deep, 3 plane split		400	.060		9.50	2.96	.66	13.12	15.60
7170		Straight split	1000	400	.060		13.15	2.96	.66	16.77	19.60
7180	1	Small unit, 4" x 18" x 10" deep, 3 plane split	Property	400	.060		20.50	2.96	.66	24.12	27.50
7190		Straight split		400	.060		15.80	2.96	.66	19.42	22.50
7200		Cap unit, 3 plane split		300	.080		18.55	3.95	.88	23.38	27.50
7210		Cap unit, straight split	- i 🗼	300	.080		18.55	3.95	.88	23.38	27.50
7250		Geo-grid soil reinforcement 4' x 50'	2 Clab	22500	.001	4 1	.66	.03		.69	.78
7255	1	Geo-grid soil reinforcement 6' x 150'	2 Clab	22500	.001	S.F.	.74	.03		.77	.86
20	2	0.04 Motal Crib Dotaining Walls									1

#### 32 32 26 - Metal Crib Retaining Walls

### 32 32 26.10 Metal Bin Retaining Walls

0010	METAL BIN RETAINING WALLS									
0011	Aluminized steel bin, excavation									
0020	and backfill not included, 10' wide									
0100	4' high, 5.5' deep	. B-13	650	.086	S.E.	34.50	4.28	3.22	42	48
0200	8' high, 5.5' deep		615	.091		40	4.52	3.40	47.92	54.50
0300	10' high, 7.7' deep		580	.097		44.50	4.79	3.61	52.90	60
0400	12' high, 7.7' deep		530	.106		48	5.25	3.95	57.20	65
0500	16' high, 7.7' deep		515	.109		50.50	5.40	4.06	59.96	68.50
0600	16' high, 9.9' deep		500	.112		56.50	5.55	4.19	66.24	75
0700			470	.119		63.50	5.90	4.45	73.85	83.50
0800	20' high, 12.1' deep		460	.122		55.50	6.05	4.55	66.10	75
0900	24' high, 12.1' deep		455	.123		59	6.10	4.60	69.70	78.50
1000	24' high, 14.3' deep		450	.124	11	83.50	6.20	4.65	94.35	106
1100	28' high, 14.3' deep		440	.127	+ 1	86.50	6.30	4.76	97.56	110
1300	For plain galvanized bin type walls, deduct			İ		10%		1		