22 01 Operation and Maintenance of Plumbing

00.0	4 00 40 Poilers Consul	-		Labor-	Heit	Metarial	2022 Bare Costs	Total	Total Incl O&P
	1 02.10 Boilers, General	Crew	Output	Hours	Unit	Material	Labor Equipment	Total	Ind U&r
0010	BOILERS, GENERAL, Prices do not include flue piping, elec. wiring,								
0020	gas or oil piping, boiler base, pad, or tankless unless noted							· ' · · · · · '	
0100	Boiler H.P.: 10 KW = 34 lb./steam/hr. = 33,475 BTU/hr.								
0150	To convert SFR to BTU rating: Hot water, 150 x SFR;					}			
0160	Forced hot water, 180 x SFR; steam, 240 x SFR								
22 O	1 02.20 Labor Adjustment Factors								
0010	LABOR ADJUSTMENT FACTORS (For Div. 21, 22 and 23) R2201	02-20							
0100	Labor factors: The below are reasonable suggestions, but								
0110	each project must be evaluated for its own peculiarities, and								
0120	the adjustments be increased or decreased depending on the								
0130	severity of the special conditions.								
1000	Add to labor for elevated installation (Above floor level)								
1080	10' to 14.5' high	I					10%		
1100	15' to 19.5' high		Ì				20% -		
1120	20' to 24.5' high						25%		*
1140	25' to 29.5' high						35%		
1160	30' to 34.5' high						40%		
1180	35' to 39.5' high						50%		
1200	40' and higher	-	1	1 1		1	55%		
2000	Add to labor for crawl space			1 1		1	3370		
2100	3' high	,				1 !	40%		
2140	i 3 ingli 4' high		1				30%		
		1	1			1	3070		
3000	Add to labor for multi-story building For new construction (No elevator available)						· · · · · · · · · · · · · · · · · · ·		
3010							5%		
3100	Add for floors 3 thru 10	1					10%		
3110	Add for floors 11 thru 15		1	1.		ý . 1	15%		
3120	Add for floors 16 thru 20		1	1 1		1			
3130	Add for floors 21 thru 30	1	1	1 1		1	20%		
3140	Add for floors 31 and up		1				30%		1
3170	For existing structure (Elevator available)	2					, 0 0/		^.
3180	Add for work on floor 3 and above						2%		
4000	Add to labor for working in existing occupied buildings								
4100	Hospital						35%		
4140	Office building			4			25% : - ;		4
4180	School						20%		
4220	Factory or warehouse						15%		
4260	Multi dwelling						15%		
5000	Add to labor, miscellaneous								
5100	Cramped shaft	1.					35%		
5140	Congested area	ï					15%		
5180	Excessive heat or cold	1					30%		
9000	Labor factors: The above are reasonable suggestions, but								
9010	each project should be evaluated for its own peculiarities.								
9100	Other factors to be considered are:								
9140	Movement of material and equipment through finished areas								
9180	Equipment room								
9220	Aftic space								
9260	No service road			,					
9300	Poor unloading/storage area								
9340	Congested site area/heavy traffic								
. 0 10	- congosion and droay matter	1							1