10 73 Protective Covers

1	0	73	16	_	Canop	ies
---	---	----	----	---	-------	-----

			Daily	Labor-		2022 Bare Costs				Total	
10 7	3 16.20 Metal Canopies	Crew	Output	Hours	Unit	Material	Labor	Equipment	Total	Incl O&P	
1700	12' x 40'	K-2	.60	40	Ea.	6,225	2,350	630	9,205	11,100	
1900	For free standing units, add	1			1	20%	10%				
2300	Aluminum entrance canopies, flat soffit, .032"										
2500	3'-6" x 4'-0", clear anodized	2 Carp	4	4	Eo.	1,500	225		1,725	1,975	
2700	Bronze anodized	: 1	4	4		1,375	225		1,600	1,825	
3000	Polyurethane painted	1	4	4		1,700	225		1,925	2,200	
3300	4'-6" x 10'-0", clear anodized	1	2	8		2,825	450		3,275	3,775	
3500	Bronze anodized		2	8		2,600	450		3,050	3,550	
3700	Polyurethane painted	1 +	2	8		291	450		741	990	
4000	Wall downspout, 10 L.F., clear anodized	1 Carp	7	1.143		204	64.50		268.50	320	
4300	Bronze anodized		7	1.143		291 -	64.50		355.50	415	
4500	Polyurethane painted	1 0	7	1.143	÷.	291	64.50		355.50	415	
7000	Carport, baked vinyl finish, .032", 20' x 10', no foundations, flat panel	. K-2	: 4	6	Cor	2,800	350	94.50	3,244.50	3,725	
7250	Insulated flat panel		2	12	"	1,650	705	189	2,544	3,075	
7500	Walkway cover, to 12' wide, stl., vinyl finish, .032", no fndtns., flat	1	250	.096	S.F.	58.50 .	5.65	1.51	65.66	74.50	
7750	Arched	1 +	200	.120	"	57.50	7.05	1.89	66.44	76.50	

10 74 Manufactured Exterior Specialties

10 74 23 - Cupolas

10 74 23.10 Wood Cupolas

0010	WOOD CUPOLAS									
0020	Stock units, pine, painted, 18" sq., 28" high, alum. roof	1 Carp	4.10	1.951	Ea.	249	110		359	440
0100	Copper roof		3.80	2.105	200	259	119		378	460
0300	23" square, 33" high, aluminum roof		3.70	2.162		385	. 122		507	600
0400	Соррет гооб		3.30	2.424		625	136		761	890
0600	30" square, 37" high, aluminum roof		3.70	2.162		610	122	1	732	850
0700	Copper roof		3.30	2.424		630	136		766	895
0900	Hexagonal, 31" wide, 46" high, copper roof		4	2		1,125	113		1,238	1,400
1000	36" wide, 50" high, copper roof	1	3.50	2.286		1,275	129		1,404	1,600
1200	For deluxe stock units, add to above				-	25%				
1400	For custom built units, add to above				i i	50%	50%			
400										

10 74 29 - Steeples

10 74 29.10 Prefabricated Steeples

0010	PREFABRICATED STEEPLES										
4000	Steeples, translucent fiberglass, 30" square, 15' high	F-3	. 2	20	Ea.	. 1,525	1,150	990	3,665	:	4,500
4150	, 25' high		1.80	22.222	:	5,600	1,275	1,100	7,975		9,275
4350	Opaque fiberglass, 24" square, 14' high		. 2	20	į	1,500	1,150	990	3,640		4,475
4500	28' high	1	1.80	22.222,		7,300	1,275	1,100	9,675		11,100
4600	Aluminum, baked finish, 16" square, 14' high					6,100			6,100		6,700
4620	20' high, 3'-6" base					10,600			10,600		11,700
4640	35' high, 8' base				-	38,000			38,000		41,800
4660	60' high, 14' base					94,500			94,500		104,000
4680	152' high, custom					711,000			711,000	:	782,000
4700	Porcelain enamel steeples, custom, 40' high	F-3	.50	80		14,400	4,625	3,975	23,000		27,000
4800	60' high	, "	.30	133	¥	18,500	7,700	6,600	32,800		39,200

10 74 46 - Window Wells

10 74 46.10 Area Window Wells

0010	AREA WINDOW WELLS, Galvanized steel								
0020	20 ga., 3'-2" wide, 1' deep	1 Sswk	29	.276	Ea.	17.80	17.05	34.85	46
0100	2' deep		23	.348		425	21.50	446.50	505