

01 56 Temporary Barriers and Enclosures

01 56 13 – Temporary Air Barriers

01 56 13.60 Tarpaulins

		Daily Crew	Labor- Output	Hours	Unit	Material	2022 Bare Costs Labor	Equipment	Total	Total Incl O&P
0010	TARPAULINS									
0020	Cotton duck, 10-13.13 oz./S.Y., 6' x 8'				S.F.	.73			.73	.80
0050	30' x 30'					.34			.34	.37
0100	Polyvinyl coated nylon, 14-18 oz., minimum					1.12			1.12	1.23
0150	Maximum					1.18			1.18	1.30
0200	Reinforced polyethylene 3 mils thick, white					.05			.05	.06
0300	4 mils thick, white, clear or black					.08			.08	.09
0400	5.5 mils thick, clear					.08			.08	.09
0500	White, fire retardant					.48			.48	.53
0600	12 mils, oil resistant, fire retardant					.39			.39	.43
0700	8.5 mils, black					.31			.31	.34
0710	Woven polyethylene, 6 mils thick					.07			.07	.08
0730	Polyester reinforced w/integral fastening system, 11 mils thick					.16			.16	.18
0740	Polyethylene, reflective, 23 mils thick					1.03			1.03	1.13

01 56 13.90 Winter Protection

0010	WINTER PROTECTION									
0100	Framing to close openings	2 Clab	500	.032	S.F.	.71	1.46		2.17	2.95
0200	Tarpaulins hung over scaffolding, 8 uses, not incl. scaffolding		1500	.011		.19	.49		.68	.93
0250	Tarpaulin polyester reinf. w/integral fastening system, 11 mils thick		1600	.010		.19	.46		.65	.89
0300	Prefab fiberglass panels, steel frame, 8 uses		1200	.013		3.14	.61		3.75	4.36

01 56 16 – Temporary Dust Barriers

01 56 16.10 Dust Barriers, Temporary

0010	DUST BARRIERS, TEMPORARY, erect and dismantle									
0020	Spring loaded telescoping pole & head, to 12', erect and dismantle	1 Clab	240	.033	Ea.		1.52		1.52	2.26
0025	Cost per day (based upon 250 days)				Day	.32			.32	.35
0030	To 21', erect and dismantle	1 Clab	240	.033	Ea.		1.52		1.52	2.26
0035	Cost per day (based upon 250 days)				Day	.75			.75	.82
0040	Accessories, caution tape reel, erect and dismantle	1 Clab	480	.017	Ea.		.76		.76	1.13
0045	Cost per day (based upon 250 days)				Day	.35			.35	.38
0060	Foam rail and connector, erect and dismantle	1 Clab	240	.033	Ea.		1.52		1.52	2.26
0065	Cost per day (based upon 250 days)				Day	.10			.10	.11
0070	Caution tape	1 Clab	384	.021	C.L.F.	2.61	.95		3.56	4.28
0080	Zipper, standard duty		60	.133	Ea.	11	6.10		17.10	21
0090	Heavy duty		48	.167	"	11.10	7.60		18.70	23.50
0100	Polyethylene sheet, 4 mil		37	.216	Sq.	4.40	9.85		14.25	19.55
0110	6 mil		37	.216	"	6	9.85		15.85	21.50
1000	Dust partition, 6 mil polyethylene, 1" x 3" frame	2 Corp	2000	.008	S.F.	.37	.45		.82	1.07
1080	2" x 4" frame	"	2000	.008	"	.55	.45		1	1.27
1085	Negative air machine, 1800 CFM				Ea.	900			900	990
1090	Adhesive strip application, 2" width	1 Clab	192	.042	C.L.F.	10.95	1.90		12.85	14.90
4000	Dust & infectious control partition, adj. to 10' high, obscured, 4' panel	2 Corp	90	.178	Ea.	580	10		590	655
4010	3' panel		90	.178		550	10		560	620
4020	2' panel		90	.178		430	10		440	490
4030	1' panel	1 Corp	90	.089		285	5		290	320
4040	6" panel	"	90	.089		265	5		270	299
4050	2' panel with HEPA filtered discharge port	2 Corp	90	.178		500	10		510	565
4060	3' panel with 32" door		90	.178		895	10		905	1,000
4070	4' panel with 36" door		90	.178		995	10		1,005	1,125
4080	4'-6" panel with 44" door		90	.178		1,200	10		1,210	1,350
4090	Hinged corner		80	.200		185	11.25		196.25	221
4100	Outside corner		80	.200		150	11.25		161.25	182
4110	T post		80	.200		150	11.25		161.25	182