## 06 16 Sheathing

06 16 36 - Wood Pane	<b>Product Sheathing</b>
----------------------	--------------------------

				Daily	Labor-		2022 Bare Costs				Total
_	36.10 Sheathing		Crew	Output	Hours	Unit	Material	Labor	Equipment	Total	Incl 0&P
4555	Pneumatic nailed	G	2 Carp	1736	.009	S.F.	.47	.52		.99	1.29
4600	5/8" thick	G		1300	.012		1.07	.69		1.76	2.21
4605	Pneumatic nailed	G	1 1	1586	.010		1.07	.57		1.64	2.03
4610	On walls, 7/16" thick	G		1200	.013		.47	.75		1.22	1.64
4615	Pneumatic nailed	G	diameter and control of	1488	.011		.47	.61		1.08	1.42
4620	1/2" thick	G		1195	.013		.47	.75		1.22	1.64
4625	Pneumatic nailed	G		1325	.012		.47	.68		1.15	1.53
4630	5/8" thick	G		1050	.015		1.07	.86		1.93	2.46
4635	Pneumatic nailed	G		1302	.012		1.07	.69		1.76	2.21
4700	Oriented strand board, factory laminated W.R. barrier, on roof, 1/2" thick	G		1400	.011		1.37	.64		2.01	2.47
4705 .	Pneumatic nailed	G		1736	.009		1.37	.52		1.89	2.28
4720	5/8" thick	G		1300	.012		2.47	.69		3.16	3.75
4725	Pneumatic nailed	G		1586	.010		2.47	.57		3.04	3.57
4730	5/8" thick, T&G	G		1150	.014		1.83	.78		2.61	3.18
4735	Pneumatic nailed, T&G	G		1400	.011		1.83	.64		2.47	2.97
4740	On walls, 7/16" thick	G		1200	.013		1.11	.75		1.86	2.34
4745	Pneumatic nailed .	G		1488	.011		1.11	.61		1.72	2.12
4750	1/2" thick	G		1195	.013		1.37	.75		2.12	2.63
4755	Pneumatic nailed	G	-	1325	.012	- i	1.37	.68		2.05	2.52
4800	Joint sealant tape, 3-1/2"		11	7600	.002	L.F.	.30	.12		.42	.51
4810	Joint sealant tape, 6"		1 🕸	7600	.002	"	.57	.12		.69	.81

## 06 16 43 - Gypsum Sheathing

## 06 16 43.10 Gypsum Sheathing

0010	GYPSUM SHEATHING									
0020	Gypsum, weatherproof, 1/2" thick	2 Co	rp 1125	.014	S.F.	.52	.80	1	.32	1.76
0040	With embedded glass mats	. "	1100	.015	. "	.62	.82	, 1	.44	1.90

# 06 17 Shop-Fabricated Structural Wood

### 06 17 33 - Wood I-Joists

### 06 17 33.10 Wood and Composite I-Joists

0010	WOOD AND COMPOSITE I-JOISTS							
0100	Plywood webs, incl. bridging & blocking, panels 24" OC							
1200	15' to 24' span, 50 psf live load	F-5	2400	.013 SF Flr.	4.82	.76	5.58	6.45
1300	55 psf live load		2250	.014	5.05	.81	5.86	6.80
1400	24' to 30' span, 45 psf live load		2600	.012	5.85	.70	6.55	7.45
1500	55 psf live load	+	2400	.013	8.55	.76 ;	9.31	10.55

### 06 17 53 - Shop-Fabricated Wood Trusses

### 06 17 53.10 Roof Trusses

0010	ROOF TRUSSES									
0100	Fink (W) or King post type, 2'-0" OC									
0200	Metal plate connected, 4 in 12 slope									
0210	24' to 29' span .	F-3	3000	.013	SF Flr.	3.26	.77	.66	4.69	5.45
0300	30' to 43' span	11	3000	.013		4.93	.77	.66	6.36	7.35
0400	44' to 60' span	1 +	3000	.013		4.75	.77	.66	6.18	7.10
0700	Glued and nailed, add	1			₩	50%				