09 29 Gypsum Board Panels

09 29 10.30 Gypsum Board		Crew	Daily Output	Labor-	Unit	Material	2022 Bare Costs Labor Equipment	Total	Total Incl O&P
4060	Mold resistant	2 Carp	300	.053	S.F.	.98	3	3.98	5.
4100	3 layers, 1/2" thick	Leap		.071		1.54	4	5.54	7.1
4110	Mold resistant		225	.071		1.33	4	5.33	7.
4150	5/8" thick	11	210	.076		1.18	4.29	5.47	7.
4160	Mold resistant		210	.076		1.48	4.29	5.77	8
5050	For 1" thick coreboard on columns		480	.033		.73	1.88	2.61	3.
5100	For foil-backed board, add	,	100	.000		.20	7.00	.20	
5200	For work over 8' high, add	2 Carp	3060	.005		*	.29	.29	
5270	For textured spray, add	2 Lath	1600	.010	1 1	.05	.56	.61	
5300	For distribution cost 3 stories and above, add per story	2 Carp		.003	i		.15	.15	
5350	For finishing inner corners, add	1	950	.017	L.F.	.11	.95	1.06	1.
5355	For finishing outer corners, add		1250	.013		.39	.72	1.11	1.
5500	For acoustical sealant, add per bead	· 1 Carp	500	.016	4	.03	.90	.93	1.
5550	Sealant, 1 quart tube	;			Ea.	5.55		5.55	6.
6000	Gypsum sound dampening panels					,			39
6010	1/2" thick on walls, multi-layer, lightweight, no finish included	2 Carp	1500	.011	S.F.	1.65	.60	2.25	2.
6015	Taped and finished (level 4 finish)		725	.022	1	1.70	1.24	2.94	3.
6020	With compound skim coat (level 5 finish)		580	.028	.	1.76	1.55	3.31	4.
6025	5/8" thick on walls, for wood studs, no finish included		1500	.011		1.76	.60	2.36	2.
6030	Taped and finished (level 4 finish)	1 1	725	.022	1 1	1.81	1.24	3.05	3.
6035	With compound skim coat (level 5 finish)	: :	580	.028		1.87	1.55	3.42	4.
6040	For metal stud, no finish included		1500	.011		1.76	.60	2.36	2.
6045	Taped and finished (level 4 finish)	1	725	.022		1.81	1.24	3.05	3.
6050	With compound skim coat (level 5 finish)	. [580	.028		1.87	1.55	3.42	4.
6055	Abuse resist, no finish included	i	1500	.011		1.70	.60	2.30	2.
6060	Taped and finished (level 4 finish)		725	.022		1.75	1.24	2.99	3.
6065	With compound skim coat (level 5 finish)		580	.028		1.81	1.55	3.36	4.
6070	Shear rated, no finish included	1 1	1500	.011		1.76	.60	2.36	2.
6075	Taped and finished (level 4 finish)		725	.022		1.81	1.24	3.05	3.
6080	With compound skim coat (level 5 finish)		580	.028		1.87	1.55	3.42	4.
6085	For SCIF applications, no finish included		1500	.011		1.56	.60	2.16	2.
6090	Taped and finished (level 4 finish)		725	.022		1.61	1.24	2.85	3.
6095	With compound skim coat (level 5 finish)	1 1	580	.028	1	1.67	1.55	3.22	4.
6100	1-3/8" thick on walls, THX certified, no finish included	1	1500	.011		8.45	.60	9.05	10.
6105	Taped and finished (level 4 finish)	1	725	.022		8.50	1.24	9.74	11.
6110	With compound skim coat (level 5 finish)		580	.028		8.60	1.55	10.15	11.
6115	5/8" thick on walls, score & snap installation, no finish included	4	2000	.008		1.76	.45	2.21	2.
6120	Taped and finished (level 4 finish)		965	.017		1.81	.93	2.74	3.
6125	With compound skim coat (level 5 finish)		775	.021	1	1.87	1.16	3.03	3.
7020	5/8" thick on ceilings, for wood joists, no finish included		1200	.013	1	1.76	.75	2.51	3.
7025	Taped and finished (level 4 finish)		510	.031	! !	1.81	1.77	3.58	4.
7030	With compound skim coat (level 5 finish)		410	.039		1.87	2.20	4.07	5.
7035	For metal joists, no finish included		1200	.013		1.76	.75	2.51	3.
7040	Taped and finished (level 4 finish)	1	510	.031		1.81	1.77	3.58	4.
7045	With compound skim coat (level 5 finish)		410	.039	1	1.87	2.20	4.07	5.
7050	Abuse resist, no finish included		1200	.013		1.70	.75	2.45	2.
7055	Taped and finished (level 4 finish)		510	.031	1	1.75	1.77	3.52	4.
7060	With compound skim coat (level 5 finish)	7	410	.039		1.81	2.20	4.01	5.
7065	Shear rated, no finish included		1200	.013		1.76	.75	2.51	3.
7070	Taped and finished (level 4 finish)		510	.031		1.81	1.77	3.58	4.
7075	With compound skim coat (level 5 finish)		410	.039		1.87	2.20	4.07	5.
7080	For SCIF applications, no finish included		1200	.013		1.56	.75	2.31	2.
7085	Taped and finished (level 4 finish)		510	.031		1.61	1.77	3.38	4.