that can be transported by hand) of up to 200' into the building and to the first or second floor is also included. If material has to be transported by other means, over greater distances, or to higher floors, an additional allowance should be considered by the estimator.

While horizontal movement is typically a sole function of distances, vertical transport introduces other variables that can significantly impact productivity. In an occupied building, the use of elevators (assuming access, size, and required protective measures are acceptable) must be understood at the time of the estimate. For new construction, hoist wait and cycle times can easily be 15 minutes and may result in scheduled access extending beyond the normal work day. Finally, all vertical transport will impose strict weight limits likely to preclude the use of any motorized material handling.

The productivity, or daily output, also assumes installation that meets manufacturer/designer/standard specifications. A time allowance for quality control checks, minor adjustments, and any task required to ensure proper function or operation is also included. For items that require connections to services, time is included for positioning, leveling, securing the unit, and making all the necessary connections (and start up where applicable) to ensure a complete installation. Estimating of the services themselves (electrical, plumbing, water, steam, hydraulics, dust collection, etc.) is separate.

In some cases, the estimator must consider the use of a crane and an appropriate crew for the installation of large or heavy items. For those situations where a crane is not included in the assigned crew and as part of the line item cost,

then equipment rental costs, mobilization and demobilization costs, and operator and support personnel costs must be considered.

Labor-Hours

The labor-hours expressed in this publication are derived by dividing the total daily labor-hours for the crew by the daily output. Based on average installation time and the assumptions listed above, the labor-hours include: direct labor, indirect labor, and nonproductive time. A typical day for a craftsman might include but is not limited to:

- Direct Work
 - Measuring and layout
 - Preparing materials
 - Actual installation
 - Quality assurance/quality control
- Indirect Work
 - Reading plans or specifications
 - Preparing space
 - Receiving materials
 - □ Material movement
 - Giving or receiving instruction
 - Miscellaneous
- Non-Work
 - Chatting
 - Personal issues
 - □ Breaks
 - Interruptions (i.e., sickness, weather, material or equipment shortages, etc.)

If any of the items for a typical day do not apply to the particular work or project situation, the estimator should make any necessary adjustments.

Final Checklist

Estimating can be a straightforward process provided you remember the basics. Here's a checklist of some of the steps you should remember to complete before finalizing your estimate.

Did you remember to:

- factor in the City Cost Index for your locale?
- take into consideration which items have been marked up and by how much?
- mark up the entire estimate sufficiently for your purposes?
- read the background information on techniques and technical matters that could impact your project time span and cost?
- include all components of your project in the final estimate?
- double check your figures for accuracy?
- call RSMeans data engineers if you have any questions about your estimate or the data you've used? Remember, Gordian stands behind all of our products, including our extensive RSMeans data solutions. If you have any questions about your estimate, about the costs you've used from our data, or even about the technical aspects of the job that may affect your estimate, feel free to call the Gordian RSMeans editors at 1.800.448.8182.

Save Time. Go Online.

For access to the latest cost data, an intuitive search, and pre-calculated location costs, take advantage of the time savings available from our online application.

rsmeans.com/online



Unit Price Section

Table of Contents								
Sect. No. Page		Sect. N	Vo.	Page	Sect. 1	Vo.	Page	
	General Requirements		04 23	Glass Unit Masonry	. 114	07 25	Weather Barriers	236
01 11	Summary of Work	. 10	04 24	Adobe Unit Masonry		07 26	Vapor Retarders	
01 21	Allowances	. 11	04 25	Unit Masonry Panels		07 27	Air Barriers	
01 31	Project Management and	1.0	04 27 04 41	Multiple-Wythe Unit Masonry		07 31	Shingles and Shakes	
01 32	Coordination	. 12	04 43	Dry-Placed Stone		07 32 07 33	Roof Tiles	
01 02	Documentation	. 14	04 51	Flue Liner Masonry		07 41	Natural Roof Coverings Roof Panels	
01 41	Regulatory Requirements		04 54	Refractory Brick Masonry	. 120	07 42	Wall Panels	
01 45	Quality Control		04 57	Masonry Fireplaces		07 44	Faced Panels	
01 51 01 52	Temporary Utilities	. 17	04 71 04 72	Manufactured Brick Masonry		07 46	Siding	
01 54	Construction Facilities		04 73	Manufactured Stone Masonry		07 51 07 52	Built-Up Bituminous Roofing	247
01 55	Vehicular Access and Parking			Metals		0/ 32	Modified Bituminous Membrane Roofing	2.48
01 56	Temporary Barriers and Enclosures		05 01	Maintenance of Metals	. 124	07 53	Elastomeric Membrane Roofing	
01 57	Temporary Controls		05 05	Common Work Results for Metals	. 124	07 54	Thermoplastic Membrane Roofing	250
01 58 01 66	Project Identification Product Storage and Handling	. 25	05 12	Structural Steel Framing		07 55	Protected Membrane Roofing	
01 00	Requirements	. 25	05 14 05 15	Structural Aluminum Framing Wire Rope Assemblies		07 56 07 57	Fluid-Applied Roofing Coated Foamed Roofing	
01 71	Examination and Preparation	. 25	05 21	Steel Joist Framing		07 58	Roll Roofing	
01 74	Cleaning and Waste Management		05 31	Steel Decking		07 61	Sheet Metal Roofing	
01 76 01 91	Protecting Installed Construction		05 35	Raceway Decking Assemblies		07 65	Flexible Flashing	
01 /1	Commissioning Existing Conditions	. 20	05 41 05 42	Structural Metal Stud Framing		07 71 07 72	Roof Specialties	
02 21	Surveys	28	05 44	Cold-Formed Metal Joist Framing Cold-Formed Metal Trusses		07 76	Roof Accessories	
02 31	Geophysical Investigations		05 51	Metal Stairs		07 81	Applied Fireproofing	
02 32	Geotechnical Investigations		05 52	Metal Railings		07 84	Firestopping	
02 41	Demolition	. 29	05 53	Metal Gratings		07 91	Preformed Joint Seals	
02 42	Removal and Diversion	25	05 54 05 55	Metal Floor Plates		07 92 07 95	Joint Sealants	
02 43	of Construction Materials Structure Moving		05 56	Metal Stair Treads and Nosings Metal Castings		0/ 93	Expansion Control	200
02 56	Site Containment		05 58	Formed Metal Fabrications		08 05	Openings Common Work Results	
02 58	Snow Control		05 71	Decorative Metal Stairs		00 03	for Openings	268
02 65	Underground Storage Tank Rmvl	. 39	05 73	Decorative Metal Railings		08 11	Metal Doors and Frames	269
02 81	Transportation and Disposal of Hazardous Materials	40	05 75	Decorative Formed Metal	. 168	08 12	Metal Frames	
02 82	Asbestos Remediation		0/ 05	Wood, Plastics & Composites		08 13 08 14	Metal Doors	
02 83	Lead Remediation	. 44	06 05	Common Work Results for Wood, Plastics, and Composites	170	08 16	Composite Doors	
02 87	Biohazard Remediation	. 45	06 11	Wood Framing		08 17	Integrated Door Opening	
02 91	Chemical Sampling, Testing and Analysis	48	06 12	Structural Panels		00.01	Assemblies	
	Concrete	. 10	06 13	Heavy Timber Construction		08 31 08 32	Access Doors and Panels	
03 01	Maintenance of Concrete	52.	06 15 06 16	Wood Decking		08 33	Coiling Doors and Grilles	
03 05	Common Work Results	. 02	06 17	Shop-Fabricated Structural Wood		08 34	Special Function Doors	
00.44	for Concrete		06 18	Glued-Laminated Construction		08 36	Panel Doors	
03 11 03 15	Concrete Forming		06 22	Millwork		08 38 08 41	Traffic Doors	
03 21	Concrete Accessories		06 25 06 26	Prefinished Paneling		08 42	Entrances and Storefronts	
03 22	Fabric and Grid Reinforcing		06 43	Board Paneling		08 43	Storefronts	
03 23	Stressed Tendon Reinforcing	. 77	06 44	Ornamental Woodwork		08 44	Curtain Wall and Glazed	
03 24	Fibrous Reinforcing		06 48	Wood Frames	. 217	08 45	Assemblies Translucent Wall and	292
03 30 03 31	Cast-In-Place Concrete		06 49	Wood Screens and Exterior Wood	219	00 43	Roof Assemblies	292
03 35	Concrete Finishing	. 84	06 51	ShuttersStructural Plastic Shapes and Plates		08 51	Metal Windows	293
03 37	Specialty Placed Concrete	86	06 52	Plastic Structural Assemblies		08 52	Wood Windows	
03 39	Concrete Curing		06 63	Plastic Railings		08 53 08 54	Plastic Windows	
03 41 03 45	Precast Structural Concrete Precast Architectural Concrete		06 65	Plastic Trim		08 62	Composite Windows Unit Skylights	
03 47	Site-Cast Concrete		06 73 06 81	Composite Decking		08 63	Metal-Framed Skylights	
03 48	Precast Concrete Specialties		00 01	Thermal & Moisture Protection	. 220	08 71	Door Hardware	303
03 51	Cast Roof Decks		07 01	Operation and Maint. of Thermal		08 75	Window Hardware	
03 52	Lightweight Concrete	0.1		and Moisture Protection	. 226	08 79 08 81	Hardware Accessories	
03 53	Roof Insulation		07 05	Common Work Results for	227	08 83	Mirrors	
03 54	Cast Underlayment		07 11	Thermal and Moisture Protection Dampproofing		08 84	Plastic Glazing	317
03 62	Non-Shrink Grouting	92	07 11	Built-up Bituminous Waterproofing		08 87	Glazing Surface Films	
03 63	Epoxy Grouting		07 13	Sheet Waterproofing	. 229	08 88 08 91	Special Function Glazing	
03 81 03 82	Concrete Cutting		07 16	Cementitious and Reactive		08 95	Vents	
UJ 04	9	>0	07 17	Waterproofing Bentonite Waterproofing		30 /0	Finishes	
04 01	Masonry Maintenance of Masonry	. 98	07 17	Water Repellents		09 01	Maintenance of Finishes	322
04 05	Common Work Results		07 21	Thermal Insulation	. 230	09 05	Common Work Results	
	for Masonry	99	07 22	Roof and Deck Insulation		00.01	for Finishes	324
04 21	Clay Unit Masonry		07 24	Exterior Insulation and Finish Systems	235	09 21	Plaster and Gypsum Board Assemblies	32.7
04 22	Concrete Unit Masonry	106		I mon systems				